

## Pre Bid Clarification No. 2 (TN-292)

(Ref. Letter No.JS9/MKTG/110601 dated 11.6.10 of M/s. Jyoti Structures Limited, Mumbai)

S. No.	Volume / Book No.	Clause	Queries	Clarifications
1.	--	--	Please confirm that sufficient spare feeders are available in AC & DC distribution boards in Bikaner, Merta City & Hindaun Sub-stations.	Confirmed.
2.	--	--	Please furnish existing earthmat layout for Bikaner, Merta City & Hindaun sub-station to assess the earthing quantity in present scope.	The earthmat shall be extended in extended switchyard portion with spacing mentioned in the scope of respective sub-station.
3.	--	--	We understand that no leveling work is envisaged in Merta City & Hindaun Sub-station. Leveling work is required only in Bikaner sub-station as per scope of work. Please confirm.	Confirmed.
4.	<b>400 kV GSS Bikaner</b>		Please confirm scope of dismantling of fencing and road at Bikaner sub-station. Drawing provided with tender [RVPN/EHV/TN-292/DRG-2(A)] is not sufficient to access the same.	Refer Item S. No. (K)9 of Civil Works of Vol.II, Part-1 for Fencing & drawing No.RVPN/EHV/TN-292/DRG-2(A) & 3 for present scope of road work.
5.	<b>400 kV GSS Bikaner</b>		In price schedule under road work 7M & 2.5 M wide roads are mentioned which are not required as per scope. As per layout drawing [RVPN/EHV/TN-292/DRG-2(A)] only 5 M, 3.75M & 3M wide road are required to be extended.	Road sizes to be extended are as per drawing(s) of respective sub-station.
6.	<b>400 kV GSS Hindaun</b>		Kindly confirm scope of dismantling of fencing and road at Hindaun sub-station. Drawing provided with tender [RVPN/EHV/TN-292/DRG-2(B)] is not sufficient to access the same.	Refer Item S. No. (K)9 of Civil Works of Vol.II, Part-1 for Fencing & drawing No.RVPN/EHV/TN-292/DRG-2(B) for present scope of road work.
7.	<b>400 kV GSS Hindaun</b>		In price schedule under road work 7M, 5 M & 3 M wide roads are mentioned which are not required as per scope. As per layout drawing [RVPN/EHV/TN-292/DRG-2(B)] only 3.75M & 2.5M wide road are required to be extended.	Road sizes to be extended are as per drawing(s) of respective sub-station.
8.	<b>400 kV GSS Merta City</b>		Kindly confirm scope of dismantling of fencing and road at Merta City Sub-station. Drawing provided with tender [RVPN/EHV/TN-292/DRG-2(C)] is not sufficient to assess the same.	Refer Item S. No. (K)9 of Civil Works of Vol.II, Part-1 for Fencing & drawing No.RVPN/EHV/TN-292/DRG-2(C) for present scope of road work.
9.	<b>400 kV GSS Merta City</b>		In price schedule under road work 5M, 3 M & 2.5 M wide roads are mentioned which are not required as per scope. As per layout drawing [RVPN/EHV/TN-292/DRG-2(C)] only 7M & 3.75 M wide road are required to be extended.	Road sizes to be extended are as per drawing(s) of respective sub-station.